

TABLE 5

The river headgate diversion requirement per acre of land for the Group 2, 3, and 4 Lands served from the Duchesne River system is 4.00 acre-feet per acre annually from direct flow and shall be diverted in accordance with the following delivery schedule.

Period		Duty		Delivery	
Date (1)	No. Days (2)	CFS/Acres (3)	Ac.Ft./Day (4)	Ac.Ft./Period (5)	Accum.Ac.Ft. (6)
Apr. 1-15	15	1/250	.00793	.119	.119
Apr. 16-30	15	1/200	.00992	.149	.268
May 1-10	10	1/125	.01586	.159	.426
May 11-20	10	1/90	.02203	.220	.647
May 21-31	11	1/80	.02479	.273	.919
June 1-10	10	1/70	.02834	.283	1.203
June 11-20	10	1/70	.02834	.283	1.486
June 21-30	10	1/75	.02645	.265	1.751
July 1-10	10	1/75	.02645	.265	2.015
July 11-20	10	1/80	.02479	.248	2.263
July 21-31	11	1/80	.02479	.273	2.536
Aug. 1-15	15	1/80	.02479	.372	2.908
Aug. 16-31	16	1/85	.02333	.373	3.281
Sep. 1-15	15	1/100	.01983	.297	3.578
Sep. 16-30	15	1/150	.01322	.198	3.777
Oct. 1-15	15	1/250	.00793	.119	3.895
Oct. 16-31	16	1/300	.00661	.106	4.001